

**GES-DIRTGLUE – PRODUCT TESTIMONIAL: FOR “ MASONPROOF”**

Dear Mr S Flinn,

As you are aware we have been trialing your GES product “Mason-Proof” to assist us with Masonary, Blocks, Bricks, & Plaster wall Water-Proofing solutions over the past 12 months.

**Our Trial sites;**

1. **GJ Gardner Build:** Sloped Section / Two Story / with Block Wall basement  
Address: 51 Discovery drive, Fletcher NSW 2285.

**Action Plan:**

- Water-Proof the Ground floor Basement Walls
- *Negative Walls (Inside Wall)*
- Positive Walls (Outside Wall facing the Ag-Soil & Water pressure side)

GES MasonProof - Waterproofing application process went ahead in January 2017  
Moisture trial testing was performed in November 2017, showed moisture readings;  
Positive Wall Readings: Tested & showed moisture at between Low 290 to 395 high  
Negative Wall Reading: Tested & showed moisture at between Low 190 to 290 high  
The Minimum Aust-Housing Moisture Reading Standard: Is Fewer than 600

**Solution:**

Ges-MasonProof was applied at an application rate of 14 to 1 litre of MP

**Summary Outcome;**

August/2017; 8 months on, The walls are still dry,  
Further Tests: Feb 2018 in our 2<sup>nd</sup> tests we performed, Again these walls are still dry at the same readings, following a wet 2018 winter season.  
In our mind a positive result for us as a business.

2. **GJ Gardner Build: Home Dwelling**

Divided by a Masonary Brick center wall, Between home living & Car Garage  
Address: Elcho Street, Hamilton Newcastle NSW 2300

**Action Plan:**

- Water Proof Center Brick Divider walls, Between Living Side & Garage,  
Current problem, Water leaking through flashings & Moisture in in the brick wall.

**Solution:**

- Step one; GJ Builders sealed all cracks & gaps in the Center line Brick wall.
- GES-Dirtglue Applicators; Used MasonProof to water proof the Masonary Bricks  
MasonProof Application Mix ratio 14 to 1.
- Application Date: 3<sup>rd</sup> April 2018
- Inspection Date: 4<sup>th</sup> April 2018  
Which included a Water Splash test onto the exterior outside walls and Internal walls.

**Summary Outcome;**

The home owners supplied their own recycled Bricks from an 80 year old Melbourne factory

Most of these bricks had defects, cracks and a lot of moisture in them, which added significantly to the problem.

***GES-Dirtglue offered excellent Sales & Tech support through the following;***

- An on site inspection & Appraisal process
- Solutions and advice to solve the Water Dampness issues
- Picking the right product: MasonProof
- And working through how to fix and apply MP to the site.
- Overall the Home is still water tight, No signs of dampness.
- We have a very happy customer.
- We are very grateful for the support and professional service provided to us by GES-Dirtglue.

Kind regards,

Mark Eddy

Managing Director

**G.J Gardner Homes Newcastle**

Trial Site 1). 51 Discovery Drive, Fletcher NSW

**Before;**



**After,** We Waterproofed with MasonProof, Note the Soil Earth works up to the Outer Walls.





Trial site 2). Elcho Street, Hamilton, Newcastle NSW

**Before;**



Mark Eddy Building Ltd T/A G.J.Gardner Homes Newcastle  
154 Hannell Street, Wickham NSW 2293 P 02 4929 0100 E [newcastle@gjgardner.com.au](mailto:newcastle@gjgardner.com.au) ABN 66 087 823 961







After; MasonProof is applied, Check the Water beads to show it working.



Mark Eddy Building Ltd T/A G.J.Gardner Homes Newcastle  
154 Hannell Street, Wickham NSW 2293 P 02 4929 0100 E [newcastle@gjgardner.com.au](mailto:newcastle@gjgardner.com.au) ABN 66 087 823 961